

- 1. ASSEMBLY TO BE APPROVED BY THE DEPT. OF HEALTH SERVICES, OFFICE OF DRINKING WATER AND CITY OF OCEANSIDE WATER UTILITIES.
- 2. ASSEMBLY SHALL BE INSTALLED IMMEDIATELY DOWNSTREAM OF THE METER WITHIN 18".
- 3. NO CONNECTION BETWEEN THE METER AND ASSEMBLY IS PERMITTED.
- 4. RED BRASS FROM METER THROUGH RP DEVICE
- 5. ALL BURIED BRASS TO BE WRAPPED IN PURPLE 6 MIL POLYETHYLENE.
- 6. PAINT ALL ABOVE GROUND PIPING SAFETY PURPLE.
- 7. WARNING TAGS CHRISTY'S MODEL ID-MAX-P2-RC007.

THIS ASSEMBLY SHALL BE INSPECTED BY THE WATER UTILITIES DEPARTMENT. AFTER WATER UTILITIES DEPARTMENT'S APPROVAL ASSEMBLY SHALL BE TESTED BY A CITY APPROVED TESTER. THE DEVELOPER/OWNER IS RESPONSIBLE FOR THE COST OF TESTING THE ASSEMBLY. THERE AFTER, THE ASSEMBLY SHALL BE TESTED ANNUALLY AT THE OWNER'S EXPENSE. THE TEST REPORT IS TO BE SUBMITTED TO THE CITY WATER UTILITIES DEPARTMENT. PHONE # 760-435-5864

Revision	Ву	Approved	Date	CITY OF OCEANSIDE		
08/30/04	AC				Stevan E Strapac	9/17/17
06/04/07	AC			REDUCED PRESSURE PRINCIPLE ASSEMBLY (2" & SMALLER)	CITY ENGINEER	Date
09/23/10	DW				OTANDADD.	
09/29/15	IN				STANDARD DRAWING NO.	₹W-7
07/01/17	SM		08/01/17		DRAWING NO. 1	X V V I